BRUHAT BENGALURU MAHANAGARA PALIKE
EXECUTIVE ENGINEER (ELECRICALS) DASARAHALLI ZONE
SCHEDULE-B

dent Number: BBMP/2021-22/EL/WORK_INDENT50081

ame O Work:Annual Maintanance of street lights package D-4 in Bagalagunte ward no 14

SNo	Item Name	Unit	Estimate Quantity	Rates Quoted by Contractor M/s. NINGEGOWDA M J (CHOWDESHWARI ELECTRICALS) In Figures (Rs.)	In Words (Rs.)
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. 36/40 W fluorescent tube light street lighting system.	Each	582	685	Rupees Six Hundred Eighty Five Only
2	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. 125W HPMV Park lighting system.	Each	104	756	Rupees Seven Hundred Fifty Six Only
3	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed belowPoles with 250W HPSV street lighting system.	Each	2642	1010	Rupees One Thousand and Ten Only
4	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below 400 watts HPSV street light /High mast lighting system.	Each	128	1118	Rupees One Thousand One Hundred and Eighteen Only

For CHOWDESHWARI ELECTRICALS

Proprietor

Executive Engineer (Elc)
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone

Scanned by CamScanner

5	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches, wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards and, switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 24 Watt to 40 Watt LED Park/ street lighting system.	Each	168	800	Rupees Eight Hundred and Eighty Only
6	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches, wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards and, switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 40 Watt to 65 W LED street Light lighting system.	Each	265	1147	Rupees One Thousand One Hundred And Forty Seven Only
7	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches, wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards and, switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 90W LED street light lighting system.	Each	121	1377	Rupees One Thousand Three Hundred and Seventy Seven Only
8	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches, wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards and, switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for110/120 watt LED street light lighting system	Each	1	1575	Rupees One Thousand Five Hundred and Seventy Five Only
9	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches, wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards and, switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 150/180 watt LED street light /High mast lighting system.	Each	1	1871	Rupees One Thousand Eight Hundred and Seventy one Only
10	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having internally Embedded gasket on all sides and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cutout with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility 300mmx450mmx214mm	Each	10	5127	Rupees Five thousand One Hundred and Twenty Two Seven Only

For CHOWDARY & CHOWDARY

Executive Engineer (E...
Bruhath Bengalore Mahanagara...
... Zone

Scanned by CamScanner

	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947 100 to 125Amps	Each	22	7200	Rupees Seven thousand Two Hundred Only
12	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898 50-63 Amps SP	Each	23	723	Rupees Seven Hundred Twenty Three Only
13	Supplying and fixing Microprocessor Based Astronomical timer Switch with using necessary bolts, nuts and washers.	Each	24	4030	Rupees Four Thousand and Thirty Only
14	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS 694:confirming to latest amendments 6 sqmm	Mtr	10	70	Rupees Seventy Only
15	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.6 sqmm	Each	100	7	Rupees Seven Only

For CHOWDESHWARI ELECTRICALS

Proprietor

Executive Engineer (Ele)
Dasarahalli Zone.
Bruhat Bengaluru Mahanagara Palike

Executive Engineer (Ele)
Bruhath Bengalore Mahanagara Palike
Dasarahalli Zone

Mah
repre
referr
Block

Bruhath Bengalore Mahanagara Palike

Scanned by CamScanner